




Roofing Ventilation & Accessories

# Tile Off-Ridge Vent

## A INNOVATIVE OFF-RIDGE VENT

Designed with a higher lift to make it suitable for tile, synthetic, cedar, shake, and slate roofs.



### Features:

- ▶ Zero water entry at 110 MPH wind-driven rain.
- ▶ No additional external baffle is needed in the front of vent, saving time and money.
- ▶ 25 square inches of Net Free Venting Area per lineal foot and 100 square inches per 4 ft. unit.
- ▶ Reduces air conditioning maintenance and utility costs.
- ▶ No additional external baffle is needed in the front of the vent saving time and money.
- ▶ Reduces air conditioning maintenance costs and prevents wood rot which extends shingle and roof deck life.
- ▶ Suitable for any roof pitch from 3/12 to 12/12.
- ▶ Keeps insects and critters out.
- ▶ High Quality & Durability - Reduces customer call-backs.
- ▶ Made from durable 26-gauge galvalume steel.

**EXPAND YOUR ROOFING SYSTEM PERFORMANCE**  
**PREVENT LEAKS • PROTECT PROPERTY • ASSURE VENTILATION**



# INSTALLATION INSTRUCTIONS

## VALUE DRIVES EVERYTHING WE DO

Value drives everything we do. That's why we developed a comprehensive line of ventilation products that offer easy installation, remarkable building ventilation, lower utility costs, extended roof deck life, extreme durability, and outstanding warranties. Get more quality, more performance, and more value...from Marco Industries.™

## EASY INSTALL

See our installation online at [marcoindustries.com](http://marcoindustries.com)

1. Space vent openings evenly across ridge. The opening size should be a minimum of a 2½" by 46" cut between two sets of rafters. Note: Do not cut into rafters.
2. If tiles have previously been installed on the roof, remove the tiles around sides and top of opening to provide space to install vent as per instructions.
4. Position vent over opening in deck.
5. Fasten side and top flanges securely with minimum 1¼" standard roofing nails. Space nails approximately 4" on the center and approximately 1½" from outer edge of flange.
5. Seal flanges to sub roof membrane as per substrate manufacturer recommendations.
6. Cut tile to fit around vent and install per tile manufacturer recommendations.



### SPECS:

**Dimensions:** Width 23 1/2" - x Height 6"

**Material:** 26 - gauge galvalume

**Codes & Standards:** FL Building Code

**Roof Pitch:** Conforms to any pitch from 3/12" to 12/12"

**Color:** Black, Weatherwood, Mill

**Patents:** Pending

**Nominal Lengths:** 4'

**Net Free Area:** 25 sq. in. per Lineal ft

**Screws:** 1 3/4" Wood Type for Bottom Flange (Not included)

**Vent Hood:** Mini louvers in lower portion of hood block water.

**Interior Louver Panel:** Mini louvers in opposite direction to louvers on lower portion of hood as second water barrier

**Internal Baffle:** Placed at the top of the vent pan, the internal baffle is the third line of defense against water intrusion.



1-800-800-8590 / [Marcoindustries.com](http://Marcoindustries.com)

